

### GENERAL NOTES

1. ALL WORK SHALL CONFORM AND COMPLY WITH NYC BUILDING CODE C27-348
2. THE WORK REQUIRED UNDER THIS CONTRACT SHALL BE PERFORMED ON NORMAL WORK HOURS TIME UNLESS OTHERWISE REQUIRED BY OTHER CLAUSES OF THIS CONTRACT OR AS DIRECTED BY THE ENGINEER.
3. BEFORE COMMENCING WORK, THE CONTRACTOR SHALL CONFIRM ALL CONDITIONS AND DIMENSIONS IN THE FIELD. ANY ERRORS OR OMISSIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER.
4. BEFORE COMMENCING WORK, THE CONTRACTOR SHALL CONFIRM THE ENGINEER OF ANY AREAS WITHOUT FIREPROOFING. ALL EXPOSED STRUCTURAL STEEL AND CHIPPED-OFF FIREPROOFING SHALL BE PATCHED OR TOUCHED-UP WITH CAFCO TYPE D-C/F OR APPROVED EQUAL AS DIRECTED BY THE ENGINEER.
5. THE CONTRACTOR SHALL NOT DRILL HOLES INTO EXISTING SLABS OR STRUCTURAL MEMBERS FOR THE PURPOSE OF SUPPORTING ANY LOADS, UNLESS WRITTEN APPROVAL IS OBTAINED FROM THE ENGINEER.
6. THE CONTRACTOR SHALL PROTECT THE PUBLIC OR TENANT SPACE BELOW FROM ANY DAMAGE RESULTING FROM FLOOR DRILLING OPERATION.
7. THE CONTRACTOR SHALL REPAIR OR REPLACE EXISTING CONSTRUCTION DAMAGED IN THE PERFORMANCE OF THIS CONTRACT AT NO COST TO THE AUTHORITY AND TO THE SATISFACTION OF THE ENGINEER.
8. THE SPACE AROUND PIPES, DUCTS, ETC. PENETRATING RATED WALLS, SHALL NOT EXCEED 1/2" AND SHALL BE PACKED SOLID WITH MINERAL WOOL OR APPROVED EQUAL AND BE CLOSED OFF BY CLOSE FITTING METAL ESCUTCHEONS ON BOTH SIDES OF THE PARTITION AS REQUIRED BY NYC BUILDING CODE C27-348
9. FIRESTOPPING SHALL BE AS REQUIRED BY NYC BUILDING CODE C26-504.7.
10. REMOVE AND REPLACE EXISTING TILE AS REQUIRED FOR MECHANICAL, PLUMBING, ETC., INSTALLATIONS.
11. REFERENCE TOWER "A" IS ALSO TOWER ONE AND TOWER "B" IS ALSO TOWER TWO.

### LOCATION PLAN

